

**PRESIDENCY UNIVERSITY**  
OFFICE OF THE PLANNING AND DEVELOPMENT

Name of the work:- Polycarbonate sheet glass house for erection of a Butterfly enclosure and Fencing at Presidency University, 86/1, College Street, Kolkata- 700 073.

ESTIMATE NO:- C-09/2015-16

Sl No	Items of work	Qty.	Unit	Rate	Amount
1	<p><b>Structure:</b> (a) Supply, fitting &amp; fixing in proper position including all labour &amp; material charges of Dome Type Tubular Fabricated Structure made of G.I. Pipe of different diameters size 3X6 meters with 3 meters central height above ground level with double doors system (Doors of 1 meter wide x 2 meters height fabricated with 33 mm diameter G.I. Pipe and fitted with Rings for locking purpose) as per our drawing complete with foundation pipe and all fittings and hardware. (b) Installation Charge for Structure including Sand, Cement and Stone Chip As per direction of Engineering In Charge.</p>	1	One Item	64,000.00	64,000.00
2	<p><b>Cladding Material :</b> Supply, fitting &amp; fixing in proper position including all labour &amp; material charges of (a) 40% Nylon Insect Proof Net to cover the entire structure to be fitted with C Channel and spring. (b) 200 Micron thick Multi Layer Clear Poly Sheet for covering part of the top portion of Enclosure for prevention from rain, to be fitted with the C Channel. (c) Metallic Wire Mesh to be fixed all around Enclosure up to a height of 300 mm for protecting Insect Proof Net from rats. (d) Installation Charge for Cladding Material As per direction of Engineering In Charge.</p>	1	One Item	65,000.00	65,000.00
3	<p>Supply, fitting &amp; fixing in proper position including all labour &amp; material charges of Electric wire and all other material including switches for Pump Set and 2 Nos Light Points (BULB) with lamp shed to be fitted inside the enclosure. Connection up shed to be provided by you on your cost. As per direction of Engineering In Charge.</p>	1	One Item	4,000.00	4,000.00
4	<p><b>Supply of Plants Sapling with Fertilizer :</b> 20 Numbers Assorted Types of Plants in the market and Chemical Fertilizer for 20 Nos Plants. As per direction of Engineering In Charge.</p>	1	One Item	1,000.00	1,000.00

SI No	Items of work	Qty.	Unit	Rate	Amount
5	<b>Fogging System :</b> Supply, fitting & fixing in proper position including all labour & material charges of (a) Poly Tank 300 liters capacity outdoor type fitted with Float Valve. (b) Electric Pump Set with a capacity to cater the water requirement of 6 numbers 4 way Fogger. (c) Control Switch for Pump Set. (d) Flexible Poly Pipe with fittings connecting your water supply line to Poly Tank. (e) Inline Screen Filter 1” BSP Connection size. (f) 40 mm diameter x 6 meter PVC Pipe Line for delivery side of Pump set complete with fittings, Control Valve and End Flush etc. (g) 2 Sets 16 mm diameters X 20 Mtrs long L L D P E Lateral Pipe Line with In Line Vale, Start Connector, Rubber Grommet, End Closer, etc for fixing Foggers. (h) 6 Numbers 4 Way Fogger completes. Each discharging 28 LPM. As per direction of Engineering In Charge.	1	One Item	64,000.00	64,000.00
6	<b>Flower Beds :</b> Supply, fitting & fixing in proper position including all labour & material charges and erection of 1 meter wide x250 mm high Flower bed at both sides of Butterfly Enclosure made with Prefabricated RCC Slabs 30 mm thick. As per direction of Engineering In Charge.	1	One Item	29,500.00	29,500.00
7	<b>Fencing :</b> Supply, fitting & fixing in proper position including all labour & material charges for Fencing 3 Meters High and 6 Meter long including Foundation Pipe, Column, Top & Base Pipe, G.I. Wire Mesh, all fittings and Hardware etc. Installation Charge for Fencing Structure including Sand, Cement and Stone Chip As per direction of Engineering In Charge.	1	One Item	40,750.00	40,750.00

Total Cost= ₹2,68,250.00  
₹2,68,250.00

Rupees Two Lac Sixty-eight Thousand Two Hundred and Fifty Only.

I/We agree to carry out the work mentioned in the General Summary at par\*/

..... % ( ..... percent) above \*/ ..... % ( ..... percent) below\*  
 the rates shown in the specified estimate.

---

Signature of the Tenderer

\*Please strike out whichever is not applicable